BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of the work:-Filling of pot holes in ward no. 10 Doddabommasandra Vidyarayanpaura sub division.

Sl. No.	Approved Qty.	Description	Unit	Issued to	
				K.V. Subbareddy	
				In Figures	In Words
1	261.41	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifcations.	Cum	1768.08	Rupees One Thousand Seven Hundred Sixty Eight and Eight Paise Only
2	1745.02	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm.KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, back filling the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2, Complete as per specifications.	Sqm	302.10	Rupees Three Hundred Two and Ten Paise Only

K.V. Subbareddy
Signature of the Contractor

10/02
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

10/02